

**OCCUPATIONAL HEALTH & SAFETY ESTIMATE**

**PROJECT: QUEENSTOWN PROJECT**

ITEM	DESCRIPTION	UNIT	QTY	RATE	TOTAL
<b>1</b>	<b>Occupational Health &amp; Safety, incl. HBA</b>				
1,1	Preparation of the Contractor's site-specific Health and Safety Plan & Risk Assessment must include	Sum	1		
1,2	Allow for the necessary Workman's Compensation Fund or FEM contributions for the duration of the	Sum	1		
1,3	Principal Contractor's initial obligations in respect of the Occupational Health and Safety Act and Construction Regulations	Sum	1		
1,4	Principal Contractor's time related obligations in respect of the Occupational Health and Safety Act and Construction Regulations	Month	6		
<b>2</b>	<b>Provision of Personal Protective Equipment (PPE)</b> <b>Note: Tenderer to provide quantity for full component</b>				
2,1	Reflective vests with visible marking of contractor's	Item	1		
2,2	Hard Hats (High Density polyethylene, & 6-point	Item	1		
2,3	Safety boots/shoes (Steel-Toe)	Item	1		
2,4	Earplugs/muffs	Item	1		
2,5	Dust Mask (at least FF2 type)	Item	1		
2,6	Safety gloves	Item	1		
2,7	Ear Defenders SABS approved	Item	1		
2,8	Overall/work suit (100% Cotton)	Item	1		
2,9	Safety Redflags (for flagman)	Item	1		
2,9	Personal Fall arrest and rescue equipment with and	Item	1		
<b>3</b>	<b>Competent Personnel</b>				
3,1	Provision of a Full time Construction <b>Health and Safety Officer (SACPCMP Registered)</b>	Month	6		
3,2	Construction Manager Cr 8.1 competent person NQF	Sum	1		
3,2	SHE Representative OHS Section 17	Sum	1		
3,3	Flagman	Sum	1		
3,4	Traffic Safety Officer (TSO)	Sum	1		
3,5	Security guard	Sum	1		
<b>4</b>	<b>Cost of medical certificates and medical surveillance per employee Note:</b>				
4,1	Initial (baseline) medical examinations	Item	1		
4,2	Working at Height Medical Certificates	Item	1		
4,3	Vaccinations (Sewer work)	Sum	1		
4,4	Provision of First Aid Boxes to GSR requirements	Item	1		
4,5	Working at Height Training (All employees working at	Sum	1		
4,6	Level 2 First Aider	Month	6		
4,7	OHS (safety, health, First Aiders, Scaffolding, Excavation, Office, PPE, etc)	Sum	1		
4,8	Fire and emergency prevention signage, extinguishers	Sum	1		
<b>5</b>	<b>Adhoc: Any OHS &amp; HBA related requirements not</b>				
5,1	Printer, Paper and Ink, consumables, soap	Sum	1		
5,2	Waste bins	Item	1		
5,3	Under cover eating area	Item	1		
5,4	Fencing around full site	Sum	1		
5,5	Hoarding and netting	Sum	1		
5,6	Working at heights equipment	Sum	1		
5,7	Close out H& S files scanned electronically with original files to CHSA.	Sum	1		
<b>SUBTOTAL TAKEN FORWARD TO THE PRELIMINARIES</b>					

This list is not exhaustive and contractors may expand all levels to include all relevancy H & S expenditure. The

Clients Principal Agent Approval:

Name \_\_\_\_\_

Signature: \_\_\_\_\_

Date: \_\_\_\_\_

FOR PRINCIPAL CONTRACTOR

Principal Contractor Representatives Acceptance Name: \_\_\_\_\_

Signature:

---